

Public Notice of Application for Permit

Regulatory Branch (1145b) Post Office Box 6898 Elmendorf AFB, Alaska 99506-6898

PUBLIC NOTICE DATE: 7 February 2005

EXPIRATION DATE:

9 March 2005

REFERENCE NUMBER:

POA-2003-1081-4

WATERWAY NUMBER:

POA-1989-402-P, Campbell Creek

Interested parties are hereby notified that an application has been received for a Department of the Army permit for certain work in waters of the United States as described below and shown on the attached plan.

<u>APPLICANT</u>: Alaska Department of Transportation and Public Facilities (DOT/PF), Central Region, P.O. Box 196900, Anchorage, Alaska, 99519-6900, and Anchorage Water and Wastewater Utility (AWWU), 3000 Arctic Boulevard, Anchorage, Alaska, 99503-3898, respectively.

LOCATION: The extension of Abbott Loop Road would occur between Abbott Road and 48th Avenue. The new 48-inch water main would be placed primarily under the paved pathway on the west side of the road. Approximately 800-feet south of 48th Avenue, the water main would switch to the east side of the road. The water line would continue north on the east side from 48th Avenue to Tudor Road. The project would take place within sections 3, 4, 9, and 10, Township 12 N., Range 3 W. and sections 33, 34, and 35, Township 13 N., Range 3 W., Seward Meridian; Latitude 61.17, Longitude -149.81.

WORK: The project would be approximately 3 miles long and would include reconstruction of the two-lane road between Abbott Road and 64th Avenue, new construction of a four-lane rural roadway between 64th and 48th Avenue, installation of a 48-inch water main, and construction of multi-use pathways and other associated features. The project would require removal of approximately 250,000 cubic yards of unsuitable material and the placement of approximately 86,228 cubic yards (CY) of fill in 7.5 acres of wetland. Approximately 6,098 CY of fill would be placed in 1.3 acres of wetlands temporarily during construction. An additional 1.8 acres of wetland would be cleared permanently for dogsled trails and for visual clearance to minimize potential moose-vehicle collisions. An additional 1.7 acres of wetland would be cleared temporarily for construction purposes; vegetation is expected to re-establish after the site is vacated. Two bridges would be constructed; a 360-foot long bridge would span the North Fork of Campbell Creek and a 568-foot long bridge would span the South Fork of Campbell Creek and Dowling Tributary. Existing culverts for the North Fork of Little Campbell Creek, Lore Tributary, and Kasuun Tributary that cross the existing Abbott Loop Road would be replaced and upgraded.

<u>PURPOSE</u>: The purpose for extending Abbott Loop Road is to upgrade the existing roadway to meet current standards and to connect Abbott Road to Tudor Road. The new roadway would facilitate north-south transportation on the east side of Anchorage and help alleviate growing traffic congestion on existing roads.

The purpose of installing the 48-inch water main between Tudor Road and Abbott Road is to complete Phase IV of the Loop Water Transmission Main, the final phase of an eight-phased loop system to provide water in adequate quantities and with sufficient pressure to meet the needs within the greater Anchorage Bowl.

ADDITIONAL INFORMATION: In 2002, Anchorage voters approved a \$123 million bond for constructing critical statewide projects; among the projects approved was the extension of Abbott Loop Road to 48th Avenue. The project, also known as the Bragaw Street Extension, has been contentious but has consistently been supported in transportation studies and plans. The AWWU Phase IV water main was reviewed previously as a stand-alone project; however, controversy over the route and construction techniques stymied construction. The Abbott Loop Road project and the Phase IV water main have been combined in this review and, if authorized, the two projects would be constructed simultaneously to minimize the overall construction and facility footprints. The AWWU water line will be hung from the bridges that cross the North and South Forks of Campbell Creek and the Dowling Tributary, thereby removing the primary concern associated with the previous AWWU Phase IV proposal. DOT/PF and AWWU entered into an agreement on February 4, 2004, to specify the roles and responsibilities of the two parties. Following construction, AWWU would maintain the Phase IV pipeline through its authorization (POA-1989-402-P) and DOT/PF would maintain the Abbott Loop Extension through its authorization (POA-2003-1081-4). Work is anticipated to begin in the fall of 2005; the majority of work would take place in 2006.

Existing dog sled trails and the recently constructed Campbell Creek multi-use trail will have grade-separated crossings. Fencing and lighting have been designed to minimize moose-vehicle collisions.

No temporary fill pads would be needed for construction south of 64th Avenue. The contractor would likely need approximately six feet of working space on the east side of two of the retaining walls; however, a temporary fill pad would not be needed. These retaining walls are located at Retaining Wall III (sta 50+55 to sta 54+17) and Retaining Wall V (sta 59+50 to sta 63+65).

Permit drawings 33-34 depict the limits of the temporary fill for the area north of Dowling Road extended. Construction of the piers that will support the bridges will require temporary construction pads for the pile-driving equipment. The cranes will also work from these pads to lift the concrete girders from both ends. Piers will be pile-driven in place. North bridge piers would involve 42 total piles (twenty 60-foot piles and twenty-two 40-foot piles), and the south bridge would involve 62 total piles (forty 60-foot piles and twenty-two 40-foot piles). Temporary roads and fills outside of the permanent roadway footprint would be needed in order to construct the retaining walls and bridge piers, as shown on the permit application drawings. Based on the size of the cranes and pile-driving equipment that will likely be used by the Contractor, the following temporary fill areas will be required:

North Bridge:

- 20-foot wide gravel pad on the "outboard" side of the retaining wall to install the panels
- 50-foot wide gravel pad for the crane to work off (to lift, set, and place the bridge girders)
- 25-foot wide gravel pad running along each of the pier locations to set equipment for pile driving

- Temporary bridge would be designed and constructed by the Contractor

South Bridge:

- 10-foot wide gravel pad on the "outboard" side of the wingwall that's in the design to hold back the slopes where they are closest to the Dowling tributary
- 50-foot wide gravel pad for the crane to work off (to lift, set, and place the bridge girders)
- 25-foot wide gravel pad running along each of the pier locations to set equipment for pile driving

There are fewer temporary fills necessary around the south bridge because this location is not as confined by park boundaries, and there are less retaining walls in the design.

Temporary wetland fills have been minimized to the extent practicable, based on the size of equipment that is necessary to construct the bridge structures. The total acreage of these temporary fills is approximately 1.6 acres with approximately 1.3 acres of temporary fill in wetlands. The temporary working pads will likely be installed in the fall or winter of 2005/2006, and will be removed in the spring of 2007.

Streams along the northern project area would be crossed using temporary bridges, which would be designed to span the entire waterway. Following construction, the temporary bridges and fills would be removed, and the area restored to natural conditions, to the extent practicable.

MITIGATION: As a result of early project planning and pre-application coordination, the applicant has incorporated into the proposed project the following mitigation efforts to reduce impacts to the aquatic environment:

- 1. Two bridges will be constructed to span the north and south forks of Campbell Creek and Dowling Tributary;
 - 2. Moose passage has been incorporated into the bridge designs;
- 3. Bridge abutments and piers were located to minimize impacts to creeks and maintain the greatest buffers;
- 4. Equalizer culverts will be installed where inundated wetlands occur on both sides of the road;
- 5. Trench plugs will be installed within the pipeline trench near streams and wetlands to minimize changes in the local subsurface hydrology caused by groundwater flows within the permeable water trench materials in the pipe zone;
- 6. The road and AWWU pipeline will be constructed as one project thereby avoiding additional wetland fill estimated at approximately 11 acres;
- 7. The 30-inch AWWU water main that needs to be relocated will be suspended from the north bridge;
- 8. Retaining walls at the bridge of North Fork Campbell Creek would be used to reduce wetland fill by 0.73 acres. Additional retaining walls have been placed throughout the project to minimize impacts to wetlands;
- 9. Fully control access between 64th and 48th Avenue, with an allowance for Dowling Road to be connected from the west, to mitigate potential secondary impacts related to development of adjacent wetlands;

- 10. Biofiltration swales will be used to treat storm water;
- 11. Moose-vehicle collisions would be reduced with specific designs for fencing, lighting, clearing, and signage;
- 12. Best management practices would be required of all contractors to minimize water quality and wetland impacts during construction; and,
- 13. Construction activities would be scheduled and sequenced to avoid sensitive nesting, spawning, and rearing periods.

Additional mitigating measures have been designed to minimize potential impacts to the human environment:

- 1. Rubberized asphalt will be installed to minimize roadway noise along the area between Abbott Road and the section line of Dowling Road;
- 2. Construction on Abbott Loop Road would be phases to allow it to remain open with the exception of temporary closures limited to one block at a time;
- 3. A temporary dogsled trail would be created to minimize interruption to trail usage during construction; a permanent rerouting of the dogsled trails would be created to reconnect all existing trails;
- 4. A pedestrian tunnel would be incorporated to accommodate the existing Campbell Creek Multi-Use trail;
- 5. Extensive use of retaining wall also would avoid impacts to private property and parkland.

WATER QUALITY CERTIFICATION: A permit for the described work will not be issued until a certification or waiver of certification as required under Section 401 of the Clean Water Act (Public Law 95-217), has been received from the Alaska Department of Environmental Conservation.

COASTAL ZONE MANAGEMENT ACT CERTIFICATION: Section 307(c)(3) of the Coastal Zone, Management Act of 1972, as amended by 16 U.S.C. 1456(c)(3), requires the applicant to certify that the described activity affecting land or water uses in the Coastal Zone complies with the Alaska Coastal Management Program. A permit will not be issued until the Office of Project Management and Permitting, Department of Natural Resources has concurred with the applicant's certification.

<u>PUBLIC HEARING</u>: Any person may request, in writing, within the comment period specified in this notice, that a public hearing be held to consider this application. Requests for public hearings shall state, with particularity, reasons for holding a public hearing.

CULTURAL RESOURCES: The latest published version of the Alaska Heritage Resources Survey (AHRS) has been consulted for the presence or absence of historic properties, including those listed in or eligible for inclusion in the National Register of Historic Places. There are no listed or eligible properties in the vicinity of the worksite. Consultation of the AHRS constitutes the extent of cultural resource investigations by the District Engineer at this time, and he is otherwise unaware of the presence of such resources. This application is being coordinated with the State Historic Preservation Office (SHPO). Any comments SHPO may have concerning presently unknown archeological or historic data that may be lost or destroyed by work under the requested permit will be considered in our final assessment of the described work.

TRIBAL CONSULTATION: The Alaska District fully supports tribal self-governance and government-to-government relations between the Federal government and

Federally recognized Tribes. This notice invites participation by agencies, Tribes, and members of the public in the Federal decision-making process. In addition, Tribes with protected rights or resources that could be significantly affected by a proposed Federal action (e.g., a permit decision) have the right to consult with the Alaska District on a government-to-government basis. Views of each Tribe regarding protected rights and resources will be accorded due consideration in this process. This Public Notice serves as notification to the Tribes within the area potentially affected by the proposed work and invites their participation in the Federal decision-making process regarding the protected Tribal right or resource. Consultation may be initiated by the affected Tribe upon written request to the District Engineer during the public comment period.

ENDANGERED SPECIES: No threatened or endangered species are known to use the project area. Preliminarily, the described activity will not affect threatened or endangered species, or their critical habitat designated as endangered or threatened, under the Endangered Species Act of 1973 (87 Stat. 844). This application is being coordinated with the U.S. Fish and Wildlife Service and the National Marine Fisheries Service. Any comments they may have concerning endangered or threatened wildlife or plants or their critical habitat will be considered in our final assessment of the described work.

ESSENTIAL FISH HABITAT: The proposed work is being evaluated for possible effects to Essential Fish Habitat (EFH) pursuant to the Magnuson Stevens Fishery Conservation and Management Act of 1996 (MSFCMA), 16 U.S.C. et seq and associated federal regulations found at 50 CFR 600 Subpart K. The Alaska District includes areas of EFH as Fishery Management Plans. We have reviewed the January 20, 1999, North Pacific Fishery Management Council's Environmental Assessment to locate EFH area as identified by the National Marine Fisheries Service (NMFS).

We have determined that the described activity may adversely affect EFH; the North Fork Campbell Creek, south Fork Campbell Creek, Dowling Tributary, and the North Fork Little Campbell Creek are designated as EFH. The proposed work would affect approximately 0.01 acres of EFH for juvenile and adult salmon.

This Public Notice initiates consultation requirements with the NMFS under the MSFCMA. We have insufficient information at this time to assess the cumulative effects of the proposed work on EFH, but cumulative effects will be considered in our final assessment of the described work. Any conservation recommendations regarding EFH for federally managed fish will also be considered in our final assessment of the described work. This proposed project may also adversely affect associated species such as major prey or predator species which are not covered by Fishery Management Plans.

The applicant has avoided impacts to significant creek stretches by bridging the main salmon streams. The loss of habitat noted above relates to the realignment of the Dowling Tributary to avoid construction impacts. The applicant not return the stream to its original channel. The original channel would be destroyed during construction and would need to be re-constructed. Rather than move the creek twice, the applicant will create a new stream channel at least 8 feet from the retaining wall of the bridge. The new stream would incorporate all appropriate measures to replicate or enhance the characteristics of the original stream channel.

SPECIAL AREA DESIGNATION: None.

EVALUATION: The decision whether to issue a permit will be based on an evaluation of the probable impacts including cumulative impacts of the proposed activity and its intended use on the public interest. Evaluation of the probable impacts, which the proposed activity may have on the public interest, requires a careful weighing of all the factors that become relevant in each particular case. The

benefits, which reasonably may be expected to accrue from the proposal, must be balanced against its reasonably foreseeable detriments. The decision whether to authorize a proposal, and if so, the conditions under which it will be allowed to occur, are therefore determined by the outcome of the general balancing process. That decision should reflect the national concern for both protection and utilization of important resources. All factors, which may be relevant to the proposal, must be considered including the cumulative effects thereof. Among those are conservation, economics, aesthetics, general environmental concerns, wetlands, cultural values, fish and wildlife values, flood hazards, floodplain values, land use, navigation, shore erosion and accretion, recreation, water supply and conservation, water quality, energy needs, safety, food and fiber production, mineral needs, considerations of property ownership, and, in general, the needs and welfare of the people. For activities involving 404 discharges, a permit will be denied if the discharge that would be authorized by such permit would not comply with the Environmental Protection Agency's 404(b)(1) quidelines. Subject to the preceding sentence and any other applicable quidelines or criteria (see Sections 320.2 and 320.3), a permit will be granted unless the District Engineer determines that it would be contrary to the public interest.

The Corps of Engineers is soliciting comments from the public; Federal, State, and local agencies and officials; Indian Tribes; and other interested parties in order to consider and evaluate the impacts of this proposed activity. Any comments received will be considered by the Corps of Engineers to determine whether to issue, modify, condition or deny a permit for this proposal. To make this decision, comments are used to assess impacts on endangered species, historic properties, water quality, general environmental effects, and the other public interest factors listed above. Comments are used in the preparation of an Environmental Assessment and/or an Environmental Impact Statement pursuant to the National Environmental Policy Act. Comments are also used to determine the need for a public hearing and to determine the overall public interest of the proposed activity.

Comments on the described work, with the reference number, should reach this office no later than the expiration date of this Public Notice to become part of the record and be considered in the decision. Please contact Dr. Maureen McCrea at (907) 753-2724, toll free from within Alaska at (800) 478-2712, or by email at maureen.mccrea@poa02.usace.army.mil if further information is desired concerning this notice.

AUTHORITY: This permit will be issued or denied under the following authorities:

(X) Discharge dredged or fill material into waters of the United States - Section 404 Clean Water Act (33 U.S.C. 1344). Therefore, our public interest review will consider the guidelines set forth under Section 404(b) of the Clean Water Act (40 CFR 230).

A plan, Notice of Application for Certification of Consistency with the Alaska Coastal Management Program, and Notice of Application for State Water Quality Certification are attached to this Public Notice.

District Engineer U.S. Army, Corps of Engineers

Attachments

STATE OF ALASKA

OFFICE OF THE GOVERNOR

DEPT. OF ENVIRONMENTAL CONSERVATION

DIVISION OF WATER
401 Certification Program
Non-Point Source Water Pollution Control Program

NOTICE OF APPLICATION FOR STATE WATER QUALITY CERTIFICATION

Any applicant for a federal license or permit to conduct an activity that might result in a discharge into navigable waters, in accordance with Section 401 of the Clean Water Act of 1977 (PL95-217), also must apply for and obtain certification from the Alaska Department of Environmental Conservation that the discharge will comply with the Clean Water Act, the Alaska Water Quality Standards, and other applicable State laws. By agreement between the U.S. Army Corps of Engineers and the Department of Environmental Conservation, application for a Department of the Army permit to discharge dredged or fill material into navigable waters under Section 404 of the Clean Water Act also may serve as application for State Water Quality Certification.

Notice is hereby given that the application for a Department of the Army Permit described in the Corps of Engineers' Public Notice No. <u>POA-2003-1081-4 & POA-1989-402P</u>, <u>Campbell Creek</u>, serves as application for State Water Quality Certification from the Department of Environmental Conservation.

After reviewing the application, the Department may certify that there is reasonable assurance that the activity, and any discharge that might result, will comply with the Clean Water Act, the Alaska Water Quality Standards, and other applicable State laws. The Department also may deny or waive certification.

Any person desiring to comment on the project with respect to Water Quality Certification may submit written comments within 30 days of the date of the Corps of Engineer's Public Notice to:

Department of Environmental Conservation WQM/401 Certification 555 Cordova Street Anchorage, Alaska 99501-2617 Telephone: (907) 269-7564

FAX:

(907) 269-7508

STATE OF ALASKA

OFFICE OF THE GOVERNOR


DEPARTMENT OF NATURAL RESOURCES OFFICE OF PROJECT MANAGEMENT AND PERMITTING


ALASKA COASTAL ZONE MANAGEMENT 550 WEST 7TH AVENUE, SUITE 1660 ANCHORAGE, ALASKA 99501-3568

NOTICE OF APPLICATION FOR CERTIFICATION OF CONSISTENCY WITH THE ALASKA COASTAL MANAGEMENT PROGRAM

Notice is hereby given that a request is being filed with the Office of Project Management and Permitting for a consistency determination, as provided in Section 307(c)(3) of the Coastal Zone Management Act of 1972, as amended [16 U.S.C. 1456(c)(3)], that the project described in the Corps of Engineers Public Notice No. **POA-2003-1081-4 & POA-1989-402P, Campbell Creek,** will comply with the Alaska Coastal Management Program and that the project will be conducted in a manner consistent with that program.

The Office of Project Management and Permitting requests your comments, particularly on the proposed project's consistency with the affected local coastal district management program. For more information on the consistency review contact OPMP at (907) 269-7470 or (907) 465-3562, or visit the ACMP web site at http://www.gov.state.ak.us/gdc/Projects/projects.html.





	LEGEND		_
Œ	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	1 00	REMOVAL OF MANHOLE
②	REMOVAL OF PAVEMENT	1 0	REMOVE AND REPLACE FIRE
´ ⁄③	REMOVAL OF CURB AND GUTTER	′ _	
1	REMOVAL OF SIDEWALK	/12)	REMOVE AND RELOCATE EXISTING MONUMENTAL SIGN AND FOUNDATION
(5)	SALVAGE SIGN	(3)	•
(B)	REMOVE AND REPLACE JUNCTION BOX		ADJUST JUNCTION BOX
\D	ADJUST EXISTING MANHOLE	19	REMOVE CULVERT
Ø.	ADJUST VALVE BOX TO FINISH GRADE	(15)	SALVAGE SIGNAL SYSTEM COMPLETE
(9	CLEARING AND GRUBBING	169	PROTECT IN PLACE

ABBREVIATIONS								
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	
AVE	AVENUE	EP	EDGE OF PAVEMENT	MHFL	MANHOLE FRAME AND LID	SHLD'R	SHOULDER	
BLVD	BOULEVARD	EVC	END OF VERTICAL CURVE	MIN	MINIMUM	SSMH	SANITARY SEWER MANHOLE	
Вм	BENCH MARK	F&G	FRAME AND GRATE	ос	ON CENTER	ST	STREET	
вус	BEGINNING OF VERTICAL CURVE	Fål	FURNISH AND INSTALL	PC	POINT OF CURVATURE	STA	STATION	
СВМН	CATCH BASIN MANHOLE	F&L	FRAME AND LID	PCC	PORTLAND CEMENT CONCRETE	ТВ	TEST BORE	
C&G	CURB AND GUTTER	FI	FIELD INLET	РТ	POINT OF TANGENCY	TBC	TOP BACK OF CURB	
CIR	CIRCLE	GCB1	GRATE AND CATCH BASIN INLET	PVI	POINT OF VERTICAL CURVE	TR	TRANSITION	
Ę.	CENTER LINE	GV	GATE VALVE	R	RADIUS	VB	VALVE BOX	
CMP	CORRUGATED METAL PIPE	HORIZ	HORIZONTAL	ROW	RIGHT-OF-WAY	vc	VERTICAL CURVE	
CSP	CORRUGATED STEEL PIPE	HP	HIGH POINT	RT	RIGHT	VT	VERTICAL	
CRR	CURB RAMP REFERENCE POINT	INV	INVERT	s	SOUTH	VPC	VERTICAL POINT OF CURVATURE	
DIP	DUCTILE IRON PIPE	LT	LEFT	SDCB	STORM DRAIN CATCH BASIN	VPI	VERTICAL POINT OF INTERSECTION	
ε	EAST	MAX	MUMIXAM	SDMH	STORM DRAIN MANHOLE	VPT	VERTICAL POINT OF TANGENCY	
ELEV	ELEVATION	мЕ	MATCH EXISTING	SE	SIDEWALK EDGE	w	WEST	

CHODI EM	THE LEGEL						
SUPPLEMENTAL LEGEND							
DESCRIPTION	EXISTING	PROPOSED					
EDGE OF GRAVEL ROAD							
EDGE OF PAVEMENT		mmmmm					
EDGE OF SHRUBS	~~~~	~~~~					
ELECTRIC METER	©						
ELECTRIC PEDESTAL	E						
LUMINAIRE	•	0→					
OVERHEAD ELECTRIC							
SANITARY SEWER CLEANOUT	0						
SIGNAL POLE W/MAST ARM & LUMINAIRE	C	0-+					
STORM DRAIN CATCH BASIN MANHOLE	G G	44					
STORM DRAIN FIELD INLET	•	0					
TEST BORING	O ^{TB} -#						
RETAINING WALL							
WETLAND FILL AREAS		777					

CORPS FILE No.: POA-2003-1081-4 & POA-1989-402-P

NAME: Alaska Department of Transportation and Public Facilities

PROJECT: ABBOTT LOOP ROAD


EXTENSION


LOCATION: S3/4/9/10, T12N, R3W, S33/34, T13N, R3W, S.M. Anchorage, Ak WATERBODY: Campbell Creek/Little


Campbell Creek


DATE: 1-31-2005 SHEET: 2 of 49


P:\Projects\D58411\ENVIRONMENTAL\COE-DDT\COE-DDT.dwg JAN 31 2005 16:12:54 (MJB)














:\Projects\D58411\ENVIRONMENTAL\COE-DDT\COE-DDT.dwg JAN 31 2005 16:12:54 (MJB)


DATE: 1-31-2005


SHEET: 7 of 49














UNCLASSIFIED EXCAVATION - CUT

GENERAL UNCLASSIFIED EXCAVATION NOTES:

1. CROSS HATCHED AREA IS INCLUDED IN THE ESTIMATED BACKFILL QUANTITIES, BUT IS NOT EXCAVATED OR PAID FOR AS UNCLASSIFIED EXAVATION, PAYMENT FOR EXCAVATION OF HATCHED AREA IS INCIDENTAL TO UNCLASSIFIED EXCAVATION.

CORPS FILE No.: POA-2003-1081-4 &

POA-1989-402-P

NAME: Alaska Department of Trans-

portation and Public Facilities

PROJECT: ABBOTT LOOP ROAD

EXTENSION

LOCATION: S33/34, T13N, R3W, S.M.


Anchorage, Alaska


WATERBODY: Campbell Creek/Little


Campbell Creek


DATE: 1-31-2005 SHEET: 10 of 49


:\Projects\D58411\ENVIRONMENTAL\COE-DDT\COE-DDT.dwg JAN 31 2005 16:12:54 (MJB)


















































































NOTE:

- CONSTRUCT CULVERT AT THE NATURAL STREAM BED SLOPE OF 1.02%
- BEDDING MATERIAL SHALL SIMULATE EXISTING STREAM BEDDING CONDITIONS OR AS DIRECTED BY THE ENGINEER, AT A BURIAL DEPTH OF 2.0'





1

NORTH FORK LITTLE CAMPBELL CREEK CULVERT DETAIL

NTS

CORPS FILE No.: POA-2003-1081-4 &

POA-1989-402-P

NAME: Alaska Department of Trans-

portation and Public Facilities

PROJECT: ABBOTT LOOP ROAD

EXTENSION

LOCATION: S9/10, T12N, R3W, S.M.


Anchorage, Alaska

WATERBODY: North Fork Little

Campbell Creek


DATE: 1-31-2005 SHEET: 39 of 44


:\Projects\D58411\ENVIRONMENTAL\COE-DDT\COE-DDT.dwg JAN 31 2005 16:12:54 (MJB)



NOTE:

- 1. CONSTRUCT CULVERT AT A 1.79% SLOPE
- 2. BEDDING MATERIAL SHALL SIMULATE EXISTING STREAM BEDDING CONDITIONS OR AS DIRECTED BY THE ENGINEER, AT A BURIAL DEPTH OF 1.6'





(1

LORE TRIBUTARY CULVERT DETAIL

NTS

CORPS FILE No.: POA-2003-1081-4 &

POA-1989-402-P

NAME: Alaska Department of Trans-

portation and Public Facilities

PROJECT: ABBOTT LOOP ROAD

EXTENSION


LOCATION: S9/10, T12N, R3W, S.M.

Anchorage, Alaska

WATERBODY: Lore Tributary


DATE: 1-31-2005 SHEET: 41 of 49


:\Projects\D58411\ENVIRONMENTAL\COE-DDT\COE-DDT.dwg JAN 31 2005 16:12:54 (MJB)



NOTE:

 EXISTING INVERTS WERE KEPT THE SAME TO KEEP UPSTREAM WETLANDS INTACT.





1

KASUUN TRIBUTARY CULVERT DETAIL

NT:

CORPS FILE No.: POA-2003-1081-4 &

POA-1989-402-P

NAME: Alaska Department of Trans-

portation and Public Facilities

PROJECT: ABBOTT LOOP ROAD

EXTENSION


LOCATION: S3/4, T12N, R3W, S.M.


Anchorage, Alaska


WATERBODY: Kasuun Tributary


DATE: 1-31-2005


SHEET: 43 of 49











CULVERT DIVERSION NOTE:

- USE PLASTIC LINER ALONG THE ENTIRE LENGTH AND WIDTH OF THE TEMPORARY DIVERSION CHANNEL.
- 2. CONSTRUCT CHANNEL AT A MINIMUM GRADE OF 0.5 PERCENT.
- 3. DO NOT CONSTRUCT WITH LONGITUDINAL JOINTS IF USING A PLASTIC UNER. BURY THE UPSTREAM EDGE OF THE LINER A MINIMUM OF 0.5 FT DEEP AND SECURE WITH RIPRAP OR SANDBAGS.

NOTE:

THIS IS A SCHEMATIC DRAWING. COORDINATE LOCATION OF DIVERSION CULVERT OR CHANNEL WITH PROJECT ENGINEER

CORPS FILE No.: POA-2003-1081-4 &

POA-1989-402-P

NAME: Alaska Department of Trans-

portation and Public Facilities

PROJECT: ABBOTT LOOP ROAD EXTENSION

EXTENSION


LOCATION: S3/4, T12N, R3W, S.M. Anchorage, Alaska

WATERBODY: Kasuun Tributary


NATE 1 71 2005 CUEET, 44 of


DATE: 1-31-2005

SHEET: 44 of 49




CULVERT PLAN VIEW
CULVERT AT STA "AL" 61+45





STRAIGHT (RIFFLE) TYPICAL SECTION



NOTES

DITCH LINING SHALL CONSIST OF ROUNDED RIVER GRAVEL AND SHALL BE PLACED ON THE STREAM BOTTOM TO A UNIFORM THICKNESS OF 3", BETWEEN BANKFULL ELEVATIONS. THE STREAM BED MATERIAL SHALL BE GRADED WITHIN THE FOLLOWING LIMITS:

U.S. STANDARD SIEVE 80 MM (3-INCH) 40 MM (1 1/2-INCH) 20 MM (3/4-INCH) 10 MM % PASSING BY WEIGHT
100%
20-60%
0-15%
0-5%

EXISTING VEGETATION EXCAVATED FOR CONSTRUCTION SHALL BE USED AS VEGETATIVE MATS FOR STREAM RELOCATION. PLACE VEGETATIVE MATS FROM BANKFULL ELEVATION TO 6" ABOVE TOP OF FLOODPLAIN BENCH.

CORPS FILE No.: POA-2003-1081-4 & POA-1989-402-P

NAME: Alaska Department of Transportation and Public Facilities

PROJECT: ABBOTT LOOP ROAD


EXTENSION


LOCATION: S33/34, T13N, R3W, S.M. Anchorage, Alaska


WATERBODY: Dowling Tributary

DATE: 2-4-2005


SHEET: 46 of 49







STRAIGHT (RIFFLE) TYPICAL SECTION



NOTES

DITCH LINING SHALL CONSIST OF ROUNDED RIVER GRAVEL AND SHALL BE PLACED ON THE STREAM BOTTOM TO A UNIFORM THICKNESS OF 3", BETWEEN BANKFULL ELEVATIONS. THE STREAM BED MATERIAL SHALL BE GRADED WITHIN THE FOLLOWING LIMITS:

EXISTING VEGETATION EXCAVATED FOR CONSTRUCTION SHALL BE USED AS VEGETATIVE MATS FOR STREAM RELOCATION. PLACE VEGETATIVE MATS FROM BANKFULL ELEVATION TO 6" ABOVE TOP OF FLOODPLAIN BENCH.

CORPS FILE No.: POA-2003-1081-4 &

POA-1989-402-P

NAME: Alaska Department of Transportation and Public Facilities

PROJECT: ABBOTT LOOP ROAD

EXTENSION

LOCATION: S9/10, T12N, R3W, S.M.

Anchorage, Alaska WATERBODY: Kasuun Tributary

DATE: 2-4-2005

SHEET: 48 of 49

